


Quantity	Item Name	Unit	Approved Rates of Sri. K Lakshmi Narayana Reddy	
			In figures	In words
10.00	Supplying and fixing PVC/metal conduit accessories.(3/5) (ELE SR 2021-22 Page-1, Item-1.5)	EACH	53.66	Rupees Fifty Three And Paise Sixty Six Only
134 10.00	c) 32mm deep junction box	EACH	73.18	Rupees Seventy Three And Paise Eighteen Only
135 10.00	Supplying and flush mounting teak wooden box without front plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonry patch work complete.(ELE SR 2021-22 Page-2, Item-1.6)	M	116.11	Rupees One Hundred Sixteen And Paise Eleven Only
136 10.00	b)12"x9"x3" (300x228x76)	M	109.28	Rupees One Hundred Nine And Paise Twenty Eight Only
137 20.00	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using copper PVC insulated multi strand 2x1.5Sqmm copper wire with a 6Amps flush type SP control switch shall be fixed on the existing plastic sheet/gang box, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. (ELE SR 2021-22 Page-2, Item-2.1)	EACH	286.86	Rupees Two Hundred Eighty Six And Paise Eighty Six Only
138 20.00	b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch (Each point)	EACH	401.99	Rupees Four Hundred One And Paise Ninety Nine Only
139 25.00	Supplying and wiring adopting loop system in existing PVC Conduit / casing capping using copper PVC insulated multi strand 2x1.5Sqmm copper wire without switch, the other end of the wires shall be terminated with sufficient loose length in a wood/PVC round block. complete for each outlet. (ELE SR 2021-22 Page-3, Item-2.2)	NOS	261.49	Rupees Two Hundred Sixty One And Paise Forty Nine Only
140 25.00	b) Medium point above 3Mtr up to 6Mtr from tapping point to out let via switch box	NOS	375.64	Rupees Three Hundred Seventy Five And Paise Sixty Four Only
141 3.00	2.2.3)Long point above 6Mtr upto 10Mtr from tapping point to out let via switch box	NOS	563.95	Rupees Five Hundred Sixty Three And Paise Ninety Five Only
142 5.00	2.2.4)Two outlet in a row,above 3Mtr upto 6Mtr from tapping point to out let via switches	NOS	698.60	Rupees Six Hundred Ninety Eight And Paise Sixty Only
143 5.00	2.2.5)Three outlet in a row, above 6Mts upto 10Mtr from tapping point to out let via switches box	NOS	1019.61	Rupees One Thousand Nineteen And Paise Sixty One Only



Contractor


Executive Engineer
Project Division
Yelahanka Zone

Quantity	Item Name	Unit	Approved Rates of Sri. K Lakshmi Narayana Reddy	
			In figures	In words
10.00	Suppling and fixing PVC/metal conduit deep junction boxes (P.No. 3, I.No. 1.5 of PWD Ele SR 2021-22)	NOS	50.74	Rupees Fifty And Paise Seventy Four Only
145 10.00	1.5.2) 25mm deep junction box	NOS	52.69	Rupees Fifty Two And Paise Sixty Nine Only
146 10.00	1.5.3) 32mm deep junction box	NOS	71.23	Rupees Seventy One And Paise Twenty Three Only
147 15.00	1.12)Suplay and fixing Metal Fan Box with Round Hook	NOS	169.77	Rupees One Hundred Sixty Nine And Paise Seventy Seven Only
148 6.00	Supplying and flush mounting powder coated metal box suitable for mounting modular switch plates. The box should be firmly flush mounted after due groove cutting in Brick/Stone/C.C wall (P.No. 9, I.No. 3.4 of PWD Ele SR 2021-22)	NOS	127.82	Rupees One Hundred Twenty Seven And Paise Eighty Two Only
149 5.00	3.4.2) 4-5Way	NOS	143.43	Rupees One Hundred Forty Three And Paise Forty Three Only
150 5.00	3.4.3) 6 Way	NOS	220.51	Rupees Two Hundred Twenty And Paise Fifty One Only
151 2.00	3.4.4) 8Way	NOS	260.51	Rupees Two Hundred Sixty And Paise Fifty One Only
152 3.00	3.4.5) 10-12Way	NOS	338.57	Rupees Three Hundred Thirty Eight And Paise Fifty Seven Only
153 20.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box. (ELE SR 2021-22 Page-5, Item-3.5.3)	EACH	253.68	Rupees Two Hundred Fifty Three And Paise Sixty Eight Only
154 68.00	Supplying and fixing of modular switch/ Socket/stepped electronic fan regulator/dimmer/telephone socket etc on existing modular switch plate..(ELE SR 2021-22 Page-5, Item-3.6)	EACH	91.72	Rupees Ninety One And Paise Seventy Two Only


Contractor


Executive Engineer
Project Division
Yelahanka Zone


Quantity	Item Name	Unit	Approved Rates of Sri. K Lakshmi Narayana Reddy	
			In figures	In words
15.00	3.6.2) 6A mps Two way	EACH	158.06	Rupees One Hundred Fifty Eight And Paise Six Only
156 15.00	3.6.4) Stepped fan regulator.	EACH	325.88	Rupees Three Hundred Twenty Five And Paise Eighty Eight Only
157 8.00	i) 32Amps DP switch	EACH	390.28	Rupees Three Hundred Ninety And Paise Twenty Eight Only
158 15.00	j) 6/16Amps universal socket	EACH	258.56	Rupees Two Hundred Fifty Eight And Paise Fifty Six Only
159 5.00	3.6.11) 6/16Amps universal socket	EACH	258.56	Rupees Two Hundred Fifty Eight And Paise Fifty Six Only
160 10.00	Supplying and fixing superior quality modular switch mounting polycarbonate plate with necessary supporting back plate with required nos. of machine screws, bolts nuts etc., complete on the existing metal/PVC box..(P.No. 10, I.No. 3.6 of PWD Ele SR 2021-22)	EACH	158.06	Rupees One Hundred Fifty Eight And Paise Six Only
161 10.00	3.5.2) 4 Module	EACH	181.48	Rupees One Hundred Eighty One And Paise Forty Eight Only
162 10.00	3.5.3) 6 Module	EACH	253.68	Rupees Two Hundred Fifty Three And Paise Sixty Eight Only
163 4.00	3.5.4) 8 Module	EACH	314.18	Rupees Three Hundred Fourteen And Paise Eighteen Only
164 5.00	3.5.5) 10-12 Module	EACH	377.60	Rupees Three Hundred Seventy Seven And Paise Sixty Only
165 1.00	Supplying and fixing regular MCB distribution boards on wall/ woodboard /flush mounting required clamps,bolts,nuts etc.. with provision for fixing suitable type capacity MCB's single phase /3 phase /single door with powder coated painting etc., complete (P.No. 27, I.No. 5.18 of PWD Ele SR 2021-22)	EACH	1766.02	Rupees One Thousand Seven Hundred Sixty Six And Paise Two Only

K. Luvu
Contractor

Executive Engineer
Project Division
Yelahanka Zone


Quantity	Item Name	Unit	Approved Rates of Sri. K Lakshmi Narayana Reddy	
			In figures	In words
1.00	5.18.8) 12Way SP & N	EACH	2153.37	Rupees Two Thousand One Hundred Fifty Three And Paise Thirty Seven Only
167 1.00	5.18.9) 4Way TP & N	EACH	3180.78	Rupees Three Thousand One Hundred Eighty And Paise Seventy Eight Only
168 1.00	5.18.10) 6Way TP & N	EACH	3644.24	Rupees Three Thousand Six Hundred Forty Four And Paise Twenty Four Only
169 2.00	Supplying and fixing and wiring Earth Leakage Miniature Circuit Breaker [RCCB] 240/450V up 300mA sensitivity on existing wood/panel board. (P.No. 28, I.No. 5.19 of PWD Ele SR 2021-22)	EACH	5033.64	Rupees Five Thousand Thirty Three And Paise Sixty Four Only
170 2.00	5.19.3)32-40 Amps 4 Pole	EACH	4563.35	Rupees Four Thousand Five Hundred Sixty Three And Paise Thirty Five Only
171 1.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C. cutouts and other equipment's on the meter board using 40mm dia 2.90mm thick GI pipe 2.5 mtr long buried in a pit ... The pit should be filled with equal proportion of salt and charcoal 150mm all-round the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size as per ISI specification 7.3.3. of IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 through holes of 12 mm dia (P.No.40, I.No. 6.1 of PWD Ele SR 2021-22)	EACH	3125.17	Rupees Three Thousand One Hundred Twenty Five And Paise Seventeen Only
172 1.00	Supplying fixing and wiring earth electrode for grounding of lifts, transformers, DG sets etc. using 40mm dia 2.9mm thick 2.5 mtr long GI pipe with GI funnel with mesh and suitable size reducer fixed on the top of the earth electrode. The funnel should be enclosed in a CC chamber of 400x400x400mm with a cast iron cover. The earth electrode shall have staggered holes of 12mm dia and the electrode should be covered 150mm all-round with alternate layers of salt and charcoal from the bottom of the CC chamber. The connection from the electrode is to be established through GI strip using GI bolts and nuts. (P.No.40, I.No. 6.2 of PWD Ele SR 2021-22)	EACH	4324.30	Rupees Four Thousand Three Hundred Twenty Four And Paise Thirty Only
173 40.00	Supplying and running of GI/Copper strips for grounding connections, using necessary fixing materials as required. (P.No. 55, I.No. 7.3 of PWD Ele SR 2021-22)	EACH	122.94	Rupees One Hundred Twenty Two And Paise Ninety Four Only
174 25.00	Copper strip ((7.3.6)25x3mm)	EACH	544.44	Rupees Five Hundred Forty Four And Paise Forty Four Only
175 15.00	Copper strip ((7.22.6)8SWG copper wire)	EACH	112.21	Rupees One Hundred Twelve And Paise Twenty One Only


Contractor


Executive Engineer
Project Division
Yelahanka Zone

Quantity	Item Name	Unit	Approved Rates of Sri. K Lakshmi Narayana Reddy	
			In figures	In words
6.00	Supplying of 2 feet LED PVC square batten with high quality diffuser with life of 25000 burning hours & 70% lumen maintenance with CRI>80. power input :220-240V @ 50 hz & power factor >.9 along with CE approved drivers. 5 years warranty (P.No. 34, I.No. 11.3 of PWD Ele SR 2021-22)	EACH	770.80	Rupees Seven Hundred Seventy And Paise Eighty Only
177 30.00	Supplying of recess mounting non integrated type LED down light 15-18W luminaire comprising of pressure decast/ extruded aluminium housing, with spring loaded false ceiling c/a, LED of Power/COB with CCT 6500 degree K, CRI> 70%. efficacy >100 lumen per W, 120degree beam spread, life> 25000 burning hours and Compliance to IS10322/IEC 60598, LM 79 & LM 80. The lamp compartment is enclosed with anti glare opal diffuser which enhances the lighting level. LED's are driven by HF electronic driver integrated in a separate control gear assembly., with PF > 0.95, power loss should< 5% of lamp Wage, short circuit & open circuit protection to be integrated in the circuit, THD less than 20%, Life as per LM 79. The operating input voltage should be between 130 to 275 V. BIS Approved and Tested by NABL/CPRI accredited laboratory with 2 years Warranty against any manufacturing defect working under standard electrical condition. (P.No. 34, I.No. 11.4 of PWD Ele SR 2021-22)	EACH	2265.58	Rupees Two Thousand Two Hundred Sixty Five And Paise Fifty Eight Only
178 36.00	Fixing all types and all capacities of fluorescent / false ceiling /spot light /CFL / LED fittings indoor on the wall /ceiling / rafters / girders using 23/0.0076" twin twisted PVC insulated wires, required Nos of round blocks and clamps .(P.No. 34, I.No. 13.7 of PWD Ele SR 2021-22)	EACH	123.91	Rupees One Hundred Twenty Three And Paise Ninety One Only
179 6.00	Supplying exhaust fan of 1440 RPM of 300 mm (12") size with bracket blades complete for light duty suitable for operate of 230V 50Hz, AC Supply. (P.No. 22, I.No. 6.1 of PWD Ele SR 2021-22)	EACH	1606.00	Rupees One Thousand Six Hundred Six Only
180 6.00	Cutting holes of required size in brick masonry wall for fixing of exhaust fan including providing and fixing 300 mm dia PVC pipe conforming BIS-12818 and making good the same etc. complete as per direction of Engineer-in-charge. (P.No. 128, I.No. 14.31 of PWP & IWTD SR 2021-22, Vol-II)	EACH	114.16	Rupees One Hundred Fourteen And Paise Sixteen Only
181 20.00	Supplying capacitor type ceiling fan complete with down rod blades, shackle, canopies etc., for operation on 230 volts, 50 cycles. Single phase AC supply conforming to ISS-374-1979 and with double bail bearing system. 48" Sweep (1200mm)(P.No. 22, I.No. 6.4 of PWD Ele SR 2021-22)	EACH	3072.48	Rupees Three Thousand Seventy Two And Paise Forty Eight Only
182 8.00	Supplying wall mounting fan suitable to operate at singlephase 230v AC. supply. (1200mm) 400 mm Sweep (P.No. 22, I.No. 6.5.2 of PWD Ele SR 2021-22)	EACH	2957.35	Rupees Two Thousand Nine Hundred Fifty Seven And Paise Thirty Five Only
183 12.00	Supplying and fixing 32Amps security and energy saving DP switch with key tag suitable to operate on 230 Volts, 50Hz AC supply &completely wired on existing box. (ELE SR 6 Page-6, Item-3.7)	EACH	777.63	Rupees Seven Hundred Seventy Seven And Paise Sixty Three Only
184 200.00	Wiring for lighting/power circuit using one of FRLS PVC insulated 1100V grade, multistrand copper wire with low conductor resistance single core in open or concealed system of wiring with specified IS-694:confirming to latest amendments. (ELE SR 2021-22 Page-3, Item-2.3)	M	19.51	Rupees Nineteen And Paise Fifty One Only


Contractor



Executive Engineer
Project Division
Yelahanka Zone

		Item Name	Unit	Approved Rates of Sri. K Lakshmi Narayana Reddy	
				In figures	In words
430.00	b. 1.5 sqmm		M	28.30	Rupees Twenty Eight And Paise Thirty Only
390.00	2.3.3) 2.5 sqmm		M	41.96	Rupees Forty One And Paise Ninety Six Only
187	350.00	2.3.4) 4 sqmm	M	63.42	Rupees Sixty Three And Paise Forty Two Only
188	390.00	C.6 sqmm	M	89.76	Rupees Eighty Nine And Paise Seventy Six Only
189	50.00	Supplying and fixing of PVC casing and capping on the wall or ceiling using necessary materials like bends, screws at an interval of 300mm Etc as required. (ELE SR 2021-22 Page-2, Item-1.8)	M	28.30	Rupees Twenty Eight And Paise Thirty Only
190	50.00	Supplying PVC/GI flexible conduit pipe....mm dia fixing on surface over inverted wooden plugs or phill plugs or rawl plugs and clamped using heavy gauge saddles at an interval of 300mm using NF screws and either end of the pipe terminated completely. (ELE SR 2021-22 Page-2, Item-1.9)	NOS	27.32	Rupees Twenty Seven And Paise Thirty Two Only
191	20.00	Extra for supplying 4mm thick white plastic plate and covering for junction boxes of size 110mm conduit using necessary machine screws. (ELE SR 2021-22 Page-6, Item-3.10.2)	NOS	14.64	Rupees Fourteen And Paise Sixty Four Only
192	20.00	Supplying a 50mm wooden plug, tapered from 50x50mm to 25x25mm and fixing by using binding wire before concreting a roof slab. (ELE SR 2021-22 Page-6, Item-3.11)	NOS	10.73	Rupees Ten And Paise Seventy Three Only
193	10.00	Supplying and fixing of slim box fitting, made out of CRCA Sheet metal body with locking type holder completely wired. Excluding Ballast & Flouresent Tube. 1 x 4' Tube light fitting. (ELE SR 2019-20 Page-41, Item-12.25.2)	EACH	322.96	Rupees Three Hundred Twenty Two And Paise Ninety Six Only
194	12.00	Supplying and fixing of T5 Fluorescent Tube with 14W power consumption with low 3mg Mercury content & below 40% glass content than T8 lamp & 20% less phosphor coating than T8 with initial lumen on 1350 (for 3000-6500 deg Kelvin), rated Avg life (12 Hr. Cycle) of greater than 35000 burring hours. Operating voltage range from 180V to 265V, 50Hz AC power Supply 28 watts Lamp (ELE SR 2021-22 Page-40, Item-12.18.2)	EACH	175.63	Rupees One Hundred Seventy Five And Paise Sixty Three Only


Contractor



Executive Engineer
Project Division
Yelahanka Zone

Sl. No.	Quantity	Item Name	Unit	Approved Rates of Sri. K Lakshmi Narayana Reddy	
				In figures	In words
195	1.00	Supplying, installing, testing and commissioning of Diesel Generator set with following specifications. Power rating as per standard reference condition as per-BS 5514/ISO 3046/ ISO 8528 & IS 1002/ISO 3046 Generator set specifications. Engine: Diesel generating set are rated at 1500RPM and conform to ISO 8528 specifications. The engines are radiator cooled, four stroke and multi cylinder, conforming to ISO 3046. The scope of supply includes: Electrical starter motor 12V DC Battery charging alternator, Bosch fuel system with mechanical governor, A1 Class. Spin-on lube oil filter, Spin-on dual fuel filter with water separator, Turbocharger, Charge air cooler, Silencer (Hospital grade), Dry type air cleaner, Shutoff coil, Flywheel and flywheel housing, First fill of lube oil and coolant, Safety for low lube oil pressure, Safety for high water temperature, Permissible overload of 10% for one hour in 12 hours of operation Capacity of Fuel Tank: Fuel tank suitable for 8 hours of operation Alternator: Alternator is suitable for operation at 1500 RPM, 415 V, 0.8 pf (lag) suitable for 50 Hz, 3 phase, 4 wire systems, conforming to IS/IEC 60034-1. The Alternator is	EACH	367392.03	Rupees Three Lakh(s) Sixty Seven Thousand Three Hundred Ninety Two And Paise Three Only
196	174.82	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge to the appropriate disposal area. (P.No. 169, I.No.19.57 of PWP & IWTD SR 2021-22)	CUM	65.37	Rupees Sixty Five And Paise Thirty Seven Only
197	1.00	BESCOM CHARGES	EACH	416819.04	Rupees Four Lakh(s) Sixteen Thousand Eight Hundred Nineteen And Paise Four Only
198	1.00	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid(P.No. 123, I.No. 14.3.1 of PWP & IWTD SR 2021-22) GROUND FLOOR	EACH	5737.12	Rupees Five Thousand Seven Hundred Thirty Seven And Paise Twelve Only
199	2.00	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid(P.No. 123, I.No. 14.3.1 of PWP & IWTD SR 2021-22) FIRST FLOOR	EACH	5793.71	Rupees Five Thousand Seven Hundred Ninety Three And Paise Seventy One Only
200	2.00	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required : W.C. pan with ISI marked white solid plastic seat and lid (KPWD SR 2021-22, Volume-II, Item No.14.2.1, Page No.123)	Each	4614.09	Rupees Four Thousand Six Hundred Fourteen And Paise Nine Only



Contractor


27


Executive Engineer
Project Division
Yelahanka Zone

Sl. No.	Quantity	Item Name	Unit	Approved Rates of Sri. K Lakshmi Narayana Reddy	
				In figures	In words
	2.00	Providing and fixing white vitreous china flat back or wall corner type lipped front urinal basin of 430x260x350 mm and 340x410x265 mm sizes respectively with automatic flushing cistern with standard flush pipe and C.P. brass spreaders with brass unions and G.I clamps complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required : One urinal basin with 5 litre white P.V.C. automatic flushing cistern (KPWD SR 2021-22, Volume-II, Item No.14.4.1, Page No.123)	EACH	4053.06	Rupees Four Thousand Fifty Three And Paise Six Only
202	11.00	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15mm C.P. brass pillar taps (KPWD SR 2021-22, Volume-II, Item No.14.7.1, Page No.124) GROUND FLOOR	EACH	2898.80	Rupees Two Thousand Eight Hundred Ninety Eight And Paise Eighty Only
203	2.00	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require: White Vitreous China Wash basin size 630x450 mm with a pair of 15mm C.P. brass pillar taps (KPWD SR 2021-22, Volume-II, Item No.14.7.1, Page No.124) FIRST FLOOR	EACH	2927.10	Rupees Two Thousand Nine Hundred Twenty Seven And Paise Ten Only
204	1.00	Providing and fixing Stainless Steel A ISI 304 (18/8) kitchen sink as per IS:13983 with C.I. brackets and stainless steel plug 40 mm, including painting of fittings and brackets, cutting and making good the walls wherever required : 510x1040 mm bowl depth 250 mm (P.No. 125, I.No. 14.10.1.1 of PWP & IWTD SR 2018-19)	EACH	5696.14	Rupees Five Thousand Six Hundred Ninety Six And Paise Fourteen Only
205	4000.00	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS: 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. (KPWD SR 2021-22, Volume-II, Item No.13.34)	LTR	9.27	Rupees Nine And Paise Twenty Seven Only
206	1.00	Supply and delivery of Centrifugal pumpset at site brand new best make and with discharge duty confirming to ISI standards and its latest amendments. 2 HP, Size 65x50 Head 13M, Discharge 462 LPM(P.No. 164, I.No. 46.1 of PWP & IWTD SR 2021-22)	Each	17681.64	Rupees Seventeen Thousand Six Hundred Eighty One And Paise Sixty Four Only
207	50.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge Concealed work, including cutting chases and making good the walls etc. 15mm nominal dia pipes.(I.No. 13.32.1 of PWP & IWTD SR 2021-22,1st Corrigendum and Addendum order - 21-04-2022)	MTR	350.28	Rupees Three Hundred Fifty And Paise Twenty Eight Only
208	50.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge Concealed work, including cutting chases and making good the walls etc. 20mm nominal dia pipes.(I.No. 13.32.2 of PWP & IWTD SR 2021-22,1st Corrigendum and Addendum order - 21-04-2022)	MTR	427.36	Rupees Four Hundred Twenty Seven And Paise Thirty Six Only


K. Luvu

Contractor


Executive Engineer
Project Division
Yelahanka Zone

Quantity	Item Name	Unit	Approved Rates of Sri. K Lakshmi Narayana Reddy	
			In figures	In words
50.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge Concealed work, including cutting chases and making good the walls etc. 25mm nominal dia pipes.(I.No. 13.32.3 of PWP & IWTD SR 2021-22,1st Corrigendum and Addendum order - 21-04-2022)	MTR	546.39	Rupees Five Hundred Forty Six And Paise Thirty Nine Only
210 100.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 25 mm nominal dia Pipes (KPWD SR 2021-22, Volume-II, Item No.13.31.3)	MTR	361.98	Rupees Three Hundred Sixty One And Paise Ninety Eight Only
211 100.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 32 mm nominal dia Pipes (KPWD SR 2021-22, Volume-II, Item No.13.31.4)	MTR	449.80	Rupees Four Hundred Forty Nine And Paise Eighty Only
212 50.00	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge Concealed work, including cutting chases and making good the walls etc. 32mm nominal dia pipes.(I.No. 13.32.4 of PWP & IWTD SR 2021-22,1st Corrigendum and Addendum order - 21-04-2022)	MTR	637.13	Rupees Six Hundred Thirty Seven And Paise Thirteen Only
213 3.00	Constructing brick masonry chamber of internal dimension 600x450mm and depth of 600mm (inner dimensions) with modular bricks of CD 75 in cement mortar 1:6, bed concrete 150mm thick with 1:3:6, plastering 12 mm thick with cement mortar 1:4, CC 1:2:4 coping 75mm thk for fixing CI cover & frame etc. excluding the cost of CI frame and cover.(P.No. 187, SOR CODE-T130A of PWP & IWTD SR 2021-22,Vol-V)	MTR	5013.15	Rupees Five Thousand Thirteen And Paise Fifteen Only
214 50.00	Supplying, laying and jointing HDPE pipes of specified grade and conforming to IS 4984-2016 with latest ammendments and conveying to work site including loading and unloading at both destinations and rolling and lowering into trenches, laying true to line and jointing of pipes and specials with electrofusion welding, giving hydraulic test as per relevant ISS with all lead and lifts including encasing the pipe alround to a depth of not less than 15 cms. with soft gravel or selected earth available from the excation, testing and commissioning. The rate is exclusive of required specials and fittings wherever necessary like saddle Tee, stub ends, flanged sets, bedns, reducers etc. complete (Contractor will make his own arrangements for procuring water for testing) etc HDPE Grade PE100-PN6.0,200mm dia..(P.No. 126, SOR Code-K060I of PWP & IWTD SR 2021-22,Vol-V)	MTR	985.46	Rupees Nine Hundred Eighty Five And Paise Forty Six Only
215 15.00	Providing and fixing brass bib cock of approved quality : 20 mm nominal bore (P.No. 114, I.No. 13.2.2 of PWP & IWTD SR 2021-22,Vol-II)	MTR	394.18	Rupees Three Hundred Ninety Four And Paise Eighteen Only


Contractor


Executive Engineer
Project Division
Yelahanka Zone

Sl. No.	Qty	Item Name	Unit	Approved Rates of Sri. K Lakshmi Narayana Reddy	
				In figures	In words
	5.00	Providing and fixing brass stop cock of approved quality : 20 mm nominal bore(P.No. 114, I.No. 13.3.2 of PWP & IWTDR SR 2021-22,Vol-II)	MTR	394.18	Rupees Three Hundred Ninety Four And Paise Eighteen Only
217	12.00	Providing and fixing square-mouth S.W. gully trap class SP-1 complete with C.I. grating brick masonry chamber 150 x 100 mm size P type With Non Modular common burnt clay bricks of designation 3.5 & with water tight C.I. cover with frame of 300 x300 mm size (inside) the weight of cover to be not less than 4.50 kg and frame to be not less than 2.70 kg as per standard design: (KPWR SR 2021-22, Volume-II, Item No.13.39)	EACH	2634.39	Rupees Two Thousand Six Hundred Thirty Four And Paise Thirty Nine Only
218	5.00	Providing and fixing PTMT grating of approved quality and colour Circular type 100 mm nominal dia.(P.No. 118, I.No. 13.22.1.1of PWP & IWTDR SR 2021-22,Vol-II)	NOS	102.45	Rupees One Hundred Two And Paise Forty Five Only
219	7.00	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. (P.No. 128, I.No. 14.31 of PWP & IWTDR SR 2021-22,Vol-II) GROUND FLOOR	NOS	1112.30	Rupees One Thousand One Hundred Twelve And Paise Thirty Only
220	2.00	Providing and fixing 600x450 mm beveled edge mirror of superior glass (of approved quality) complete with 6 mm thick hard board ground fixed to wooden cleats with C.P. brass screws and washers complete. (P.No. 128, I.No. 14.31 of PWP & IWTDR SR 2021-22,Vol-II) FIRST FLOOR	NOS	1112.00	Rupees One Thousand One Hundred Twelve Only
221	571.00	4 Seater Student Desk Heavy Fabricated Frame with 18mm pre laminated board top complete as per specification and the directions of Engineer-in-charge	NOS	14937.95	Rupees Fourteen Thousand Nine Hundred Thirty Seven And Paise Ninety Five Only
222		Applicable GST Charges			

K. Lakshmi

[Signature]

Contractor

Executive Engineer
Project Division
Yelahanka Zone